

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-10021-00-00  
Spot: SWNE Sec/Twnshp/Rge: 6-30S-8W  
990 feet from N Section Line, 990 feet from E Section Line  
Lease Name: POMEROY Well #: 1-6  
County: KINGMAN Total Vertical Depth: 4297 feet

Operator License No.: 34357  
Op Name: ATLAS OPERATING LLC  
Address: 15603 KUYKENDAHL, STE 200  
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	320		250 SX
PROD	5.5	4247	2630	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2011 2:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: SAND BACK 50' ABOVE THE OH AND CAP WITH 5 SKS OF CMT. RECOVER CASING. 35 SKS OF 1300, 35 SKS OF 850, CIRC CMT 300'-0

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 02/14/2011 4:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE OH WAS FILLED WITH SAND TO 4195 AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2630', AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRCULATED TO SURFACE. DID NOT CORRECT INFO ON LOCATION FOR AMOUNT OF SURFACE PIPE IN THE HOLE. SCOUT CARD REPORTS 320' OF 8".

Perfs:

Top	Bot	Thru	Comments
4247	4297	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED Form CP-2/3  
MAR 03 2011  
KCC WICHITA  
3/16

JK