

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20559-00-00  
Spot: NENENE Sec/Twnshp/Rge: 6-18S-16W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: KOBER Well #: 1  
County: RUSH Total Vertical Depth: 3560 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	235		WITH 175 SX CMT
PLG	4.5	3540		
PROD	4.5	3558	0	WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2011 1:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: ALAN CURTIS Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 463-5161

Proposed Plugging Method: RUN TBG TO 3500' & PUMP 50 SX CMT WITH 100# HULLS MIXED IN. PULL TBG TO 1000' & CIRCULATE CMT TO SURFACE. PRESSURE 8 5/8" X 4 1/2" ANNULUS WOT 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2011 4:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*WELL'S 4 1/2" CASING WAS SQUEEZED AT 240' WITH 500 SX CMT. CASING PARTED @ 540'. WORKED TBG THROUGH PART WITH MUCH DIFFICULTY.\*\*  
FOUND TD WITH TBG AT 3494'. PULLED TBG TO 3482' & PUMPED 50 SX CMT WITH 100# HULLS MIXED IN. GOOD CIRCULATION. PULLED TBG TO 1040'. PUMPED 100 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 4 1/2" CASING. PULLED TBG OUT OF HOLE. TOPPED OFF 4 1/2" WITH 25 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 3000 PSIG WITH CMT. NO ENTRY.

Perfs:

Top	Bot	Thru	Comments
3530	3538		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

RECEIVED  
MAR 10 2011

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

KCC WICHITA

RECEIVED

FEB 28 2011

KCC DODGE CITY

Form CP-273

3/18