

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20325-00-00  
Spot: E2E2SW Sec/Twnshp/Rge: 22-30S-41W  
1329 feet from S Section Line, 2982 feet from E Section Line  
Lease Name: HILTY Well #: 1-22  
County: STANTON Total Vertical Depth: 5660 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5275		WITH 2 SX CMT
SURF	8.625	1515		WITH 750 SX CMT
PROD	5.5	5656	0	WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2011 9:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 5275' WITH 2 SX CMT. SET CMT RETAINER @ 1450' & PUMP CMT TO SURFACE IN 5 1/2" & 8 5/8" ANNULAR. PUMP 25 SX CMT AT 600'. PUMP 25 SX CMT AT 300'. FILL 5 1/2" FROM 60' TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2011 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*CASING LEAK BETWEEN 1515' & 1550'.\*\* SET CIBP @ 5275' WITH 2 SX CMT. SET CMT RETAINER @ 1450' & BROKE CIRCULATION TO SURFACE, PUMPED 10 SX GEL & 300 SX CMT. CMT TO SURFACE IN 5 1/2" & 8 5/8" ANNULUS. STUNG OUT OF RETAINER, PUMP 25 SX CMT AT 600'. PUMPED 25 SX CMT AT 300'. PUMP 15 SX CMT AT 60' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5325	5330		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED

MAR 10 2011

District: 01

RECEIVED

MAR - 9 2011

KCC DODGE CITY

Signed

Jack MacLaskey KCC WICHITA  
(TECHNICIAN)

Form CP-2/3

3/18