

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23619-00-00  
Spot: W2SWSESW Sec/Twnshp/Rge: 18-7S-21W  
330 feet from S Section Line, 1530 feet from W Section Line  
Lease Name: SMITH Well #: 1  
County: GRAHAM Total Vertical Depth: 3695 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218	0	150 SX CMT
T1	2.875	3670		
PROD	5.5	3694	0	440 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2010 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 600# hulls - 11 sxs gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/23/2010 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 75 sxs 60/40 pozmix - 4% gel with 300# hulls - followed with 11 sxs gel spacer and 210 sxs cement with 150# hulls.  
Backside full of cement. Alt II cwc bottom to surface.

Perfs:

Top	Bot	Thru	Comments
3658	3670		Arbuckle
3607	3625		Conglomerate
3577	3593		Marmaton
3445	3538		LKC
3273	3275		Topeka

RECEIVED  
JAN 03 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

✓ 1/26/11

DEC 29 2010