

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23907-00-00  
Spot: SWSWNESW Sec/Twnshp/Rge: 27-7S-20W  
1640 feet from S Section Line, 1640 feet from W Section Line  
Lease Name: AVIS Well #: 1  
County: ROOKS Total Vertical Depth: 3415 feet

Operator License No.: 33306  
Op Name: BLAKE EXPLORATION, LLC  
Address: 201 S MAIN PO BOX 150  
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		

Well Type: DH UIC Docket No: Date/Time to Plug: 12/15/2010 9:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: BLAKE EXPLORATION, LLC Phone: (785) 421-2921

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 12/15/2010 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 1545' w/25 sxs.  
2nd. Plug at 870' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
DEC 21 2010  
KCC WICHITA

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

DEC 17 2010

Form CP-2/8  
12/26/11