

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22593-00-01
Spot: NESWSWSE Sec/Twnshp/Rge: 36-19S-11W
569 feet from S Section Line, 2090 feet from E Section Line
Lease Name: NEELAND B Well #: 4
County: BARTON Total Vertical Depth: 3318 feet

Operator License No.: 6768
Op Name: CARRIE EXPLORATION & DEVELOPM
Address: 210 W 22ND
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223	0	w/unknown sxs cmt
PROD	5.5	3315	0	125 SXS. COMMON.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: RON HEROLD Company: CARRIE EXPLORATION & DEVEL Phone: (913) 961-2760

Proposed Plugging Method: Emergency plug with rig over the hole - holes in casing.
Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/13/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 475' - 200'.
Ran tubing to 3000' - tied to tubing - pumped 11 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1500' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 700' - circulated cement to surface with 190 sxs cement - cement to surface on casing and on surface pipe.
Pulled tubing and topped off with 10 sxs cement.

Perfs:

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

RECEIVED
DEC 17 2010
KCC WICHITA

CM

Form CP-2/3

1/26/11

DEC 15 2010