

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-091-20870-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 20-13S-23E
3939 feet from S Section Line, 4987 feet from E Section Line
Lease Name: CEDAR CREEK Well #: 2
County: JOHNSON Total Vertical Depth: 820 feet

Operator License No.: 6146
Op Name: CEDRA CREEK PROPERTIES, INC.
Address: 8900 INDIAN CREEK PARKWAY
OVERLAND PARK, KS 66225

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/15/2010 3:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, LLC Phone: (620) 431-9212

Proposed Plugging Method: FILL THE WELL FULL OF CEMENT FROM BOTTOM TO TOP.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/15/2010 3:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

THE WELL HAD CEMENT PRESENT AT THE SURFACE WITH HOLES AND CRACKS IN IT. DRILLED THROUGH THE CEMENT INSIDE THE 2 7/8" CASING TO 210' AND HIT STEEL. PERFORATED THE 2 7/8" CASING AT 200', 125', AND 75'. RAN 1" PIPE DOWN TO 210' AND FILLED THE 2 7/8" CASING FULL OF CEMENT. HOOKED ON TO 2 7/8" CASING AND SQUEEZED CEMENT. TOTAL AMOUNT OF CEMENT USED WAS 14 SACKS.

RECEIVED

JAN 12 2011 TCH

KCC Chanute Dist. #3

Remarks: THIS WELL WAS PLUGGED AS A FEE FUND. THE LEGAL STAFF MAY REQUIRE CEDAR CREEK PROPERTIES, INC. TO REIMBURSE THE STATE FOR PLUGGING THE WELL.

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)

RECEIVED

Form CP-2/3

JAN 14 2011

1/20/11

KCC WICHITA