

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-041-20128-00-00
Spot: NWNWSENW Sec/Twnshp/Rge: 13-16S-2E
3892 feet from S Section Line, 3742 feet from E Section Line
Lease Name: GERALDINE Well #: A-1
County: DICKINSON Total Vertical Depth: 3205 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		330 SX CMT
COND	13.38	36		50 SX CMT
PLG		2488		PBTD
PROD	5.5	2600	1010	175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2010 1:00 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: _____ Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2010 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:


12/8/10 SUNFLOWER DROPPED SAND AND RIGGED UP CASING PULLERS. THEY WENT DOWN & TAGGED SAND @ 2360'. THEY CAPPED IT WITH 5 SXS. FOUND THE CONDUCTOR PIPE TO BE ABOUT 3' DOWN TO CEMENT. WORKING ON RIPPING CASING, BUT FLOOR KEEP SINKING IN. THEY WILL REGROUP IN THE MORNING. 12/9/10 SUNFLOWER RIPPED CASING @ 1010' AND LAID IT OUT. HOLE FILLED WITH DRILLING MUD TO 305'. THEY WILL SLURRY THE TOP PLUG. HILLSBORO REDMIX ARRIVED @ 3:00 PM. THE USED APPROX 5.5 YDS OF SLURRY AND FINISHED @ 4:00 PM. TK #46139 FOR 7 YDS OF SLURRY USED 5.5YDS. 12/10/10 I CHECKED TOP PLUG AND FOUND IT DOWN 30'. TALKED TO BUD DAVIS AND HE WILL COME OUT WITH A HAND MIX AND TOP OFF WELL.

Perfs:

Top	Bot	Thru	Comments
2414	2420	CSG	
2410	2414		

Remarks:
Plugged through: TBG

District: 02

Signed 
(TECHNICIAN)

RECEIVED

JAN 03 2011

KCC WICHITA

Form CP-2/3
1/26/11

JK