

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20295-00-00  
Spot: SENENW Sec/Twnshp/Rge: 12-13S-22W  
990 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: ARNOLD Well #: 1  
County: TREGO Total Vertical Depth: 4067 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	244	0	140 SX
PROD	4.5	3877	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2011 11:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: OZZIE VAN AUSDALE Company: BEAR PETROLEUM, INC. Phone: (316) 524-1027

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perfs: 2250' - 1685' - 900' - 230'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2011 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing and tagged sand at 3641'.  
Pulled tubing to 3500' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 2255' - pumped 100 sxs cement with 200# hulls.  
Pulled to 1002' - pumped 120 sxs cement with 100# hulls.  
Cement circulated out backside - shut in.  
Pumped 30 sxs cement - circulated out the Braden head - shut in.  
POOH. Topped off casing with 8 sxs cement - checked - filled up 85' down.

Perfs:

Top	Bot	Thru	Comments
3793	3802		LANSING
3704	3708		LANSING
3637	3642		LANSING
3566	3572		LANSING

RECEIVED  
FEB 02 2011  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #37522.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN)

CM

JAN 31 2011