

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21275-00-00
Spot: NESENWNE Sec/Twnshp/Rge: 25-9S-26W
700 feet from N Section Line, 1450 feet from E Section Line
Lease Name: TRANSUE Well #: 25-6
County: SHERIDAN Total Vertical Depth: 4180 feet

Operator License No.: 34151
Op Name: BRINKER ENTERPRISES, LLC
Address: 216 S MARSHALL ST
GLEN ELDER, KS 67446

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	279		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/26/2011 12:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: BRINKER ENTERPRISES, LLC Phone: (785) 545-3348

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 2320' w/25 sxs.
2nd. Plug at 1078' w/100 sxs.
3rd. Plug at 330' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED

FEB 01 2011

Form CP-2/3

KCC WICHITA

JAN 27 2011