

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23215-00-00
Spot: NENWSE Sec/Twnshp/Rge: 8-11S-16W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CHESNEY Well #: 1
County: ELLIS Total Vertical Depth: 3496 feet

Operator License No.: 32286
Op Name: BROWN, RODNEY DBA MJT OIL
Address: 115 3RD ST BOX 112
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	165	0	165 SX
PROD	4.5	3436	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2011 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLING Company: MJT OIL Phone: (785) 623-3221

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
PBTD 3402'. Perfed at 1440'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2011 2:35 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Hole was plugged off. Western Well Service washed down to 1666'.
Pulled tubing - ran back in the hole to 1490' - perfed at 1440'.
Quality rigged to tubing and pumped 30 sxs cement.
Pulled tubing to 1050'. Perforators LLC shot hole at 1050'.
Quality rigged to tubing and pumped 125 sxs to circulate cement to surface.
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 15 sxs cement with 100# hulls mixed in.
Max. P.S.I. 200#. S.I.P. 200#.
Rigged to 8 5/8" - pumped 10 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3344	3347		MARM
3275	3280		LKC
3250	3254		LKC
3226	3228		LKC
3142	3145		LKC
3046	3048		TORONTO

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5097.

Plugged through: TBG

RECEIVED
FEB 09 2011
KCC WICHITA

District: 04

Signed _____


(TECHNICIAN)

CM

Form CP-2/3

FEB 07 2011