

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-107-24148-00-00  
Spot: SWNWNESW Sec/Twnshp/Rge: 35-21S-22E  
2012 feet from S Section Line, 3648 feet from E Section Line  
Lease Name: LANHAM Well #: 11-35  
County: LINN Total Vertical Depth: 798 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	21		8 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/22/2010 2:30 PM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 228-2847

Proposed  
Plugging  
Method:

CEMENT PLUGS AT TD, 450 FEET, AND FROM 250 FEET TO SURFACE WITH GEL SPACERS.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 10/22/2010 5:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

PUMP CEMENT THROUGH DRILL PIPE AND PLACE 20 SACKS CEMENT AT 798 FEET, 52 SACKS CEMENT AT 450 FEET, AND FILL FROM 250 FEET TO SURFACE WITH CEMENT. GEL SPACERS WERE PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 115 SACKS OF CEMENT.

Perfs:

RECEIVED

FEB 11 2011 LS

KCC Chanute Dist. #3

Remarks: D&A TO COMPLY WITH EASTERN KANSAS SURFACE CASING ORDER.

Plugged through: DP

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 18 2011  
2-17-11  
KCC WICHITA