

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21624-00-00
Spot: E2NWNWNW Sec/Twnshp/Rge: 14-19S-29W
4978 feet from S Section Line, 4840 feet from E Section Line
Lease Name: EARL SPLITTER Well #: 1
County: LANE Total Vertical Depth: 4685 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4200		WITH 2 SX CMT
CIBP		4340		
SURF	8.625	255		WITH 180 SX CMT
DVT		1402		WITH 240 SX CMT
PROD	4.5	4653	0	WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2011 9:00 AM
Plug Co. License No.: 7146 Plug Co. Name: CHEYENNE OIL SERVICES, INC.
Proposal Rcvd. from: GARY MISAK Company: ABERCROMBIE Phone: (316) 833-6530

Proposed Plugging Method: SET CIBP @ 4200'. RUN TBG TO 2170' & CIRCULATE TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP CMT DOWN IT IF POSSIBLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2011 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PACKER & 420' OF TBG LEFT IN HOLE BELOW CIBP @ 4340'. SET CIBP @ 4200' WITH 2 SX CMT. RUN TBG TO 2170' & PUMP 170 SX CMT. CMT CIRCULATED TO SURFACE. PULL TBG & TOP OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 1/4 BBL. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4384	4444		MARMATON
4236	4239		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
RECEIVED
FEB 10 2011
KCC DODGE CITY
KCC DODGE CITY

Michael Maier
(TECHNICIAN)

RECEIVED
FEB 23 2011
KCC WICHITA