

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20239-00-00
Spot: SENWNE Sec/Twnshp/Rge: 13-19S-29W
4643 feet from S Section Line, 679 feet from E Section Line
Lease Name: VOSHELL Well #: 1
County: LANE Total Vertical Depth: 4670 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4050		WITH 4 SX CMT
CIBP		4590		
SURF	8.625	237		WITH 185 SX CMT
PROD	5.5	4668	0	WITH 75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2011 9:00 AM
Plug Co. License No.: 7146 Plug Co. Name: CHEYENNE OIL SERVICES, INC.
Proposal Rcvd. from: GARY MISAK Company: ABRECROMBIE Phone: (316) 833-6530

Proposed Plugging Method: SET CIBP @ 4050' WITH 2 SX CMT. RUN TBG TO 2150' & 30 SX CMT. TEST CASING. IF HOLDS PRESSURE PERFORATE CASING @ 1250'. MIX CASING VOLUME & 80 SX CMT. IF DOES NOT CIRCULATE MIX 200 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2011 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4050' WITH 4 SX CMT. RUN TBG TO 2170' & SPOT 30 SX CMT. WAIT 2 HOURS & TEST CASING TO 500# & HELD. PERFORATE @ 1240'. RUN TBG TO 1250' & PUMP 115 SX CMT. PULL TBG & TIE ONTO CASING. PUMP 80 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 300#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4610	4614		JOHNSON ZONE
4072	4366		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

FEB 10 2011

KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)
RECEIVED

FEB 23 2011

KCC WICHITA

Form CR-28