

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21581-00-00
Spot: NESWNE Sec/Twnshp/Rge: 25-19S-28W
3654 feet from S Section Line, 1628 feet from E Section Line
Lease Name: WARE Well #: 6
County: LANE Total Vertical Depth: 4679 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3742		WITH 2 SX CMT
SURF	8.625	268		WITH 180 SX CMT
DVT		1390		WITH 500 SX CMT
PROD	5.5	4672	0	WITH 245 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2011 1:00 PM
Plug Co. License No.: 7146 Plug Co. Name: CHEYENNE OIL SERVICES, INC.
Proposal Rcvd. from: GARY MISAK Company: ABERCROMBIE Phone: (316) 262-1841

Proposed Plugging Method: SET CIBP @ 4200'. RUN TBG TO 2170' & CIRCULATE TO SURFACE. PULL TBG & TOP OFF. TIED ONTO BACKSIDE & PUMP CMT DOWN IT IF POSSIBLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2011 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3742' WITH 2 SX CMT. RUN TBG TO 2170' & PUMP 225 SX CMT & 400# HULLS. CIRCULATED TO SURFACE. PULL TBG & TOP OFF WITH 40 SX CMT. BACKSIDE HEAD WAS FULL OF CMT. COULDN'T PUMP DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4302	4307		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

FEB 10 2011

KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
FEB 23 2011
KCC WICHITA