

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22671-00-00
Spot: NESESE Sec/Twnshp/Rge: 7-22S-11W
1010 feet from S Section Line, 351 feet from E Section Line
Lease Name: HAMMEKE Well #: 4
County: STAFFORD Total Vertical Depth: 3730 feet

Operator License No.: 6030
Op Name: AINSWORTH OPERATING CO.
Address: 4676 COMMERCIAL ST., SE #412
SALEM, OR 97302

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		WITH 150 SX CMT
PROD	4.5	3727	1634	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2011 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 01/21/2011 5:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 3250' & 4 SX CMT. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3613	3626		ARB
3285	3308		LKC

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

FEB 14 2011

KCC DODGE CITY

RECEIVED
FEB 23 2011

KCC WICHITA

Form CP 2/3