

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21230-00-00  
Spot: NWSE Sec/Twnshp/Rge: 5-24S-17W  
2019 feet from S Section Line, 1951 feet from E Section Line  
Lease Name: JOHNSON Well #: 3-5  
County: EDWARDS Total Vertical Depth: 4475 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	251		WITH 235 SX CMT
PROD	4.5	4455	2040	WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2011 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 4280' & 4 SX CMT. PLUG AT 1160' WITH 16 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/31/2011 2:31 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 4200' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4331	4371		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED  
FEB 10 2011  
KCC DODGE CITY

RECEIVED  
FEB 15 2011  
KCC WICHITA

Form CP-2/3