

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24602-00-01
Spot: NWNWSESW Sec/Twnshp/Rge: 33-20S-11W
1220 feet from S Section Line, 1530 feet from W Section Line
Lease Name: MEYER OWWO Well #: 2-33
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3508		
SURF	8.625	270	0	225 SX CMT 60/40 POZ, 2% GEL, 3% CC
TI	2.375	3466		
PROD	5.5	3577	1799	50 SX CMT LITE AND 150 SX CMT MIX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/14/2011 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL COMPANY L.L.C. Phone: (316) 684-8481

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2011 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded to 3320' and topped with 5 sxs cement.
Cut casing at 1799'.
Pulled casing to 1450' - tied to casing and pumped 125 sxs cement with 300# hulls.
Pulled to 575' - pumped 40 sxs cement with 100# hulls.
Pulled to 150' - pumped 80 sxs cement - circulated to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3508			
3414	3418		SIMPSON SAND
3371	3383		SIMPSON SAND

Remarks: BASIC WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

RECEIVED

(TECHNICIAN)

FEB 22 2011

CM

FEB 17 2011

KCC WICHITA Form CP-2/3