

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20161-00-00  
Spot: NWSE Sec/Twnshp/Rge: 21-24S-17W  
2017 feet from S Section Line, 1977 feet from E Section Line  
Lease Name: NEWSOM Well #: 1-21  
County: EDWARDS Total Vertical Depth: 4770 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	256		WITH 235 SX CMT
PROD	4.5	4470	2000	WITH 100 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2011 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: PLUG AT 1170' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2011 3:05 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

\*\*TOP OF FISH @ 4050'.\*\* PUMPED 35 SX CMT WITH 3% CC @ 4000'. TAGGED CMT AT 3515'. 1ST PLUG AT 1170' WITH 10 SX GEL, 100# HULLS & 50 SX CMT. 2ND PLUG AT 600' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4356	4369		MISSISSIPPI

RECEIVED  
JAN 31 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED  
JAN 26 2011  
KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)