

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19976-00-00
SW NW NW Sec/Twp/Rge Sec 3 T28S R17E
4414 (gps) feet from south section line
4713 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Stover STO 01 (gps)

County Wilson

Operator: State Of Kansas Fee Fund

Well Total Depth 1000 feet

Name & Stover Lease Project

Production Pipe: 2.375 Size Feet NA

Address _____

Surface Casing: 6.25 Size Feet NA

AB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 30 Month: 9 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-8945

Were: Clean well to TD and pump full of portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All XXXXXX Part _____ None _____

Operations Completed: Hour: _____ Day: 30 Month: 9 2010

Actual Plugging Report: A 1" cement string was washed down the outside of the production string

to 40' where the pipe hit hard. A 2nd 1" cement string was washed down the inside of the production

string to 990' where the pipe hit hard. The well was then pumped full of cement from btm to top thru these

cement strings. A total of 49 sacks of portland cement were used to plug well. The well was cut off

below plow depth and the location restored.

RECEIVED

FEB 17 2011

Remarks: Control #20110002-001

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I did observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN