

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-205- 19981-00-00  
SW NW SW NW Sec/Twp/Rge Sec 3 T28S R17E  
3292 (gps) feet from south section line  
5026 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Stover STO 06 (gps)

Operator: State Of Kansas Fee Fund

County Wilson

Name & Stover Lease Project

Well Total Depth 1000 feet

Address \_\_\_\_\_

Production Pipe: 2.375 Size Feet NA

AB oil well XXXXXX Gas Well \_\_\_\_\_

Surface Casing: 6.25 Size Feet NA

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 1 Month: 10 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-8945

Were: Clean well to TD and pump full of portland cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ TECHNICIAN None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 1 Month: 10 2010

Actual Plugging Report: A 1" cement string was lowered down the inside of the production string to 915'.

A 1" cement string was washed down the outside of the production string to 2' where the pipe tagged cement. The well was pumped full of cement from btm to top thru these cement strings. A total of 57 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20110002-006

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN

RECEIVED

FEB 17 2011

KCC WICHITA