

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-205- 19982-00-00  
SE  
SW SW NW Sec/Twp/Rge Sec 3 T28S R17E  
2861 (gps) feet from south section line  
4562 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Stover Lease Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Stover STO 07 (gps)  
County Wilson  
Well Total Depth 1000 feet  
Production Pipe: 2 Size Feet NA  
Surface Casing: 8 Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 8 Month: 10 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-8945

Were: Clean well to TD and pump full of portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 8 Month: 10 2010

Actual Plugging Report: A 1" cement string was washed down the inside of the production pipe to

950'. A 1" cement string was washed down the outside of the production pipe to 515'. The contactor

began pumping full of cement thru the cement strings but ran out. 10-15-10: Tagged cement at 30' on the

inside of the production pipe and 45' on the outside of the production pipe and finished filling with cement

thru 1" cement strings. A total of 198 sacks of portland cement were used to plug well. The well was cut

off below plow depth and the location restored.

RECEIVED

FEB 17 2011

Remarks: Control #20110002-007

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN