

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-205- 19984-00-00  
SE  
SW SW NW Sec/Twp/Rge Sec 3 T28S R17E  
3261 (gps) feet from south section line  
4558 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Stover STO 09 (gps)

County Wilson

Operator: State Of Kansas Fee Fund

Well Total Depth 1000 feet

Name & Stover Lease Project

Production Pipe: 5 Size Feet NA

Address \_\_\_\_\_

Surface Casing: 8 Size Feet NA

AB oil well XXXXXX Gas Well \_\_\_\_\_

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 14 Month: 10 2010

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-8945

Were: Clean well to TD and pump full of portland cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 14 Month: 10 2010

Actual Plugging Report: A 4" swedge was lowered down the inside of the production pipe to 500'

without any obstructions. The swedge was removed and a 1" cement string lowered down the inside of the

production pipe to 995'. A 0.5" cement string was washed down the outside of the production pipe to 355'.

The well was pumped full of cement from btm to top thru these cement strings. A total of 165 sacks of

portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

FEB 17 2011

Remarks: Control #20110002-009

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN