

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19996-00-00
SE NW SW Sec/Twp/Rge Sec 9 T28S R15E
1775 (gps) feet from south section line
4132 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Cannon Land Co. Lease Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Cannon Land Co #CAN OW2
County Wilson
Well Total Depth _____ 1000 feet
Production Pipe: NA Size Feet NA
Surface Casing: 10 Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 4 Month: 11 2010

Plugging proposal received from: Robert Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Clean well to TD and then pump full of cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part XXXXXX TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 4 Month: 11 2010

Actual Plugging Report: Set 12" surface pipe. The drill rig was moved to location and the well drilled to 735' where the drill bit hit iron. The drill pipe was removed and a 1" cement string lowered to approx 735'. The well was pumped full of cement from btm to top thru this cement string. A total of 371 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20110021-002
(If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed:

Alan M. Dunning
TECHNICIAN

RECEIVED
FEB 11 2011

KCC WICHITA