

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 01000-00-00
SW NW SW Sec/Twp/Rge Sec 9 T28S R15E
1654 (gps) feet from south section line
5153 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Cannon Land Co. Lease Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Cannon Land Co #CAN OW3
County Wilson
Well Total Depth _____ 1000 feet
Production Pipe: NA Size Feet NA
Surface Casing: 8 Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 30 Month: 11 2010

Plugging proposal received from: Robert Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Clean well to TD and then pump full of cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part XXXXXX TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 30 Month: 11 2010

Actual Plugging Report: Set 12" surface pipe. The drill rig was moved to location and the well drilled to 500' thru wood and rocks. The bit hit iron at 500'. The drill pipe was removed and a 1" cement string was lowered to 475'. The well was then pumped full of cement from btm to top thru this cement string. A total of 85 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20110021-003

(If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed:

Alan M. Dunning
TECHNICIAN

RECEIVED
FEB 07 2011

KCC WICHITA