

3 023519

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & HEGWALD II PLUGGINGAddress FEE FUNDED PLUGGINGAB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, INC.Lic. # 33749Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 8:00A.M. Day: 5 Month: 6 2009Plugging proposal received from: CLAYTON TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HAD BEEN
CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH
OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All PartTECHNICIAN
None XOperations Completed: Hour: 12:00P.M. Day: 5 Month: 6 2009Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 824'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE
2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE
2" AND 8" ANNULUS TO 520'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL
CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE
WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 174 SACKS OF
CEMENT WERE PUMPED INTO THIS WELL.

Remarks: THIS WAS GPS NO. 12. THIS WAS WELL NO. C12-30 ON THE LEASE MAP.(If additional description is necessary, use BACK of this form.)I DID NOT observe this plugging.

Signed:

Clayton P. Titel
 TECHNICIAN

RECEIVED
 FEB 28 2011
 KCC WICHITA

20090015-012