

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25347-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 8-16S-13W
730 feet from N Section Line, 2280 feet from E Section Line
Lease Name: BITTER Well #: 1-8
County: BARTON Total Vertical Depth: 3465 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3250		
SURF	8.625	891	0	350 SX CMT
T1	2.875	3406		
PROD	5.5	3461	2305	100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2011 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM, INC. Phone: (620) 792-6702

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
Cut off 5 1/2" casing at 2305'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2011 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

02/03/2011 - Sanded off bottom to 3100' - spotted 5 sxs common cement.
02/04/2011 - Cut casing at 2305'.
Pulled casing to 1653' - pumped 190 sxs cement with 300# hulls.
Pulled casing to 870' - pumped 25 sxs cement.
Pulled casing to 350' - pumped 105 sxs cement - circulated to surface.
POOH. Topped off surface casing with 10 sxs cement.
Checked 02/07/2011 fluid down 85' - will top off with cement.

Perfs:

Top	Bot	Thru	Comments
3376	3380		
3375	3381		
3215	3220		LKC
3192	3196		LKC
3166	3170		LKC

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #37256.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED
FEB 11 2011
KCC WICHITA