

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21915-00-00
Spot: N2N2SE Sec/Twnshp/Rge: 16-20S-10W
2343 feet from S Section Line, 1328 feet from E Section Line
Lease Name: WILSON Well #: 2-C
County: RICE Total Vertical Depth: 3395 feet

Operator License No.: 34360
Op Name: EC SERVICES, LLC
Address: PO BOX 543
BENTON, KS 67017

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251		
PROD	5.5	3388		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/07/2011 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OIL FIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: PRUDENT EFFORT MADE TO GET TO BOTTOM. RUN TUBING TO 1580' AND SPOT 50 SX'S CEMENT. PERFORATE AT 900' AND 300'. RUN TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 01/07/2011 11:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

CASING PARTED AT APPROX. 1580'. WORK INVOICES FROM GRESSEL OIL FIELD SERVICE INDICATED A PRUDENT EFFORT HAD BEEN MADE TO GET TO BOTTOM. PERFORATE AT 900' AND 300'. RUN TUBING TO 1580' AND SPOT 50 SX'S COMMON CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 300' AND CIRCULATE 60-40 POZ, 4% GEL CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. HAD CIRCULATION THRU-OUT JOB. TOPPED OFF ON 1-18-11 - TICKET C-37514.

Perfs:

Top	Bot	Thru	Comments
3388	3395	OH	

RECEIVED
FEB 02 2011
KCC WICHITA

Remarks: COPELAND CEMENT #C-37506. GRESSEL PERF TICKET #0766.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

JK