

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20411-00-00
Spot: NWNW Sec/Twnshp/Rge: 19-24S-16W
4625 feet from S Section Line, 4665 feet from E Section Line
Lease Name: HAWLEY Well #: 1-19
County: EDWARDS Total Vertical Depth: 4390 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	270		WITH 225 SX CMT
PROD	4.5	4389	1960	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/27/2011 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT TO BOTTOM. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2011 2:59 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 200# HULLS & 50 SX CMT TO BOTTOM. TAGGED TOC @ 3415'. 1ST PLUG AT 1120' WITH 15 SX GEL - 50 SX CMT - 50# HULLS. 2ND PLUG AT 300' WITH 50 SX CMT - 50# HULLS. 3RD PLUG AT 40' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4270	4274		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
FEB 11 2011
KCC WICHITA

District: 01

RECEIVED
JAN 28 2011
KCC DODGE CITY

Signed

Richard W. Lacey
(TECHNICIAN)