

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00728-00-00
Spot: NWNENE Sec/Twnshp/Rge: 3-11S-21W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: HEDSTROM Well #: 9
County: TREGO Total Vertical Depth: 3660 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216	0	125 SX
PROD	5.5	3660	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2011 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 470 sxs 60/40 pozmix - 4% gel - 750# hulls.
Holes in the casing at 1032' - 1063' to 2100'.
DV Tool 1536' w/500 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2011 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3238' - pumped 110 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled to 2290' - pumped 110 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled to 1020' - pumped 110 sxs 60/40 pozmix - 4% gel with 150# hulls to circulate to surface.
Pulled all tubing. Hooked to 5 1/2" casing - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 450#.
Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 400# immediately.

Perfs:

Top	Bot	Thru	Comments
3637	3640		
3400	3428		

Remarks: SWIFT SERVICES, INC.-TICKET #19602.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

FEB 28 2011

KCC WICHITA

FEB 24 2011