

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26088-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 11-14S-20W
3199 feet from S Section Line, 1080 feet from E Section Line
Lease Name: BEFORT Well #: 6
County: ELLIS Total Vertical Depth: 3862 feet

Operator License No.: 4871

Op Name: HITSCHMANN, CURTIS LEE DBA CURT'S SURF 8.625 223

Address: PO 8
GREAT BEND, KS 67530

OIL OPERATIONS

[Handwritten signature]

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/03/2011 3:00 PM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM ALM

Company: CURT'S OIL OPERATIONS

Phone: (620) 793-2540

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER

WitnessType: NONE

Date/Time Plugging Completed: 02/03/2011 6:30 PM

KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 3821' w/25 sxs.
2nd. Plug at 1530' w/25 sxs.
3rd. Plug at 775' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED
MAR 01 2011
KCC WICHITA

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

FEB 25 2011

Form CP-2/3

3/18