

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05303-00-00
Spot: SWSENE Sec/Twnshp/Rge: 34-11S-17W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: DREILING Well #: 5
County: ELLIS Total Vertical Depth: 3511 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	129	0	w/unknown sxs cmt
PROD	5.5	3505	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2011 12:30 PM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: JASON OIL COMPANY, LLC Phone: (785) 483-2025

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls - 13 sxs gel.
Log Tech perfed at 1800' - 1200' - 550'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2011 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Super Oilwell Service RIH with tubing to 3492'.
Quality rigged to tubing and pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1600'. Quality rigged to tubing and mixed and pumped 180 sxs cement with 200# hulls to circulate cement to pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 15 sxs cement.
Pumped casing to Max. P.S.I. 200#. S.I.P. 200#.
Dug out 8 5/8" casing - casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3480	3510		

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED

MAR 03 2011

Form CP-2/3

3/18

KCC WICHITA

MAR 02 2011