

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-21305-00-00  
Spot: N2NENESW Sec/Twnshp/Rge: 28-4S-42W  
2539 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: STROH Well #: 1-28  
County: CHEYENNE Total Vertical Depth: 5340 feet

Operator License No.: 31783  
Op Name: MID-CONTINENT ENERGY OPERATING  
Address: 100 W 5TH ST STE 450  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/25/2011 3:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KIRBY Company: MID-CONTINENT ENERGY OPERATING Phone: (918) 587-6363

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE Witness Type: NONE  
Date/Time Plugging Completed: 02/25/2011 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 3390' w/25 sxs.  
2nd. Plug at 2530' w/100 sxs.  
3rd. Plug at 355' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Rodie

(TECHNICIAN) RECEIVED

CM

MAR 03 2011 Form CP-2/3

KCC WICHITA

FEB 28 2011