

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01813-00-01
Spot: SESWSE Sec/Twnshp/Rge: 6-30S-8W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DICK Well #: 1
County: KINGMAN Total Vertical Depth: 4285 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3100		
SURF	8.625	239		250 SX
PROD	4.5	4285	2725	150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/21/2011 12:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND BACK TO 3810 AND 4 SKS OF CMT. RECOVER CASING SPOT 35 SKS 1300, 35 SKS 850, CIRC CMT 290. HIC 3100

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 02/21/2011 2:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3075 AND CAPPED WITH 4 SKS ~~OP~~ CMT. THE CASING WAS RECOVERED FROM 2725 AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED 275' WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4206	4224	CSG	
3866	3876	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

MAR 03 2011

Form CP-2/3

3/18

KCC WICHITA