

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00771-00-00
Spot: SWNE Sec/Twnshp/Rge: 9-30S-8W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: EVANS Well #: 1
County: KINGMAN Total Vertical Depth: 4332 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	247		
PROD	5.5	4332	474	
RBP	5.5	3850		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: MARK MOLITOR Company: MOLITOR OIL Phone: (620) 243-3543

Proposed Plugging Method: RUN TUBING TO 3850' CAP RBP WITH 10 SKS OF CMT. PULL TUBING TO 1300', PERF CASING AND SPOT 50 SKS OF CMT. PULL TUBING TO 850', SPOT 50 SKS OF CMT. PULL TUBING TO 310', AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2011 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

WELL HEAD CASING LEAK. OPERATOR INTENDED TO CHANGE OUT 750' OF CASING. RIG CREW PUT TONGS ON CASING TO TIGHTEN THE CASING BEFORE BACKOFF. THE CASING WAS TWISTED OFF AT 474'. CASING WAS LAYED OUT. RAN IN THE HOLE WITH TUBING AND GOT BACK INSIDE THE 5.5 CASING TO THE RBP AT 3850'. A 10 SK CMT PLUG WAS SPOTTED AT 3822', AND THEN PULLED TO 1290'. PERFORTORS RAN DOWN THE TUBING TO 1300' WHERE 4 HOLES WERE SHOT IN THE CASING AND 50 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 850'. WHERE 25 SKS FO CMT AND ADDITIONAL 25 SKS OF CMT WITH COTTON SEED HULLS MIXED IN THE CMT. WAITED 1.5 HOURS AND TAGGED CMT AT 820'. PULLED TUBING TO 310' AND CIRCD CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4216	4240	CSG	

RECEIVED
MAR 01 2011
KCC WICHITA

Remarks: ALLIED CMT 60/40 4% GEL

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)