

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20813-00-01
Spot: S2S2NW Sec/Twnshp/Rge: 28-29S-8W
2970 feet from S Section Line, 3960 feet from E Section Line
Lease Name: KING Well #: OWWO 1
County: KINGMAN Total Vertical Depth: 4200 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	301		250 SX
PROD	4.5	4198	2615	150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 243-3543

Proposed Plugging Method: SAND TO 3844' AND 4 SKS CMT. RECOVER CASING. PULL CASING TO 1300', SPOT 35 SKS CMT, PULL TO 850, SOT 35 SKS CMT. PULL TO 350, CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/23/2011 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A 30 SK CMT PLUG AND 100LBS OF HULLS WAS PUMPED DOWN THE CASING TO CLOSE THE PERFS. SHUT IN PRESSURE WAS 1000#. TAGGED THE TOP OF THE CMT AT 3525'. THE CASING WAS RECOVERED FROM 2615 AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3931	3938	CSG	
3894	3900	CSG	

Remarks: QWS CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
MAR 03 2011
KCC WICHITA