

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23928-00-00
Spot: N2SESE Sec/Twnshp/Rge: 32-9S-18W
1120 feet from S Section Line, 660 feet from E Section Line
Lease Name: EICHMAN Well #: 1
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 33937
Op Name: NEAL LAFON REALTY INC. DBA MERI
Address: 1475 WARD DR
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/05/2011 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: STEVE Company: MERIDIAN ENERGY IHNC. Phone: (303) 688-4022

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 03/05/2011 5:45 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 3755' w/25 sxs.
2nd. Plug at 1560' w/25 sxs.
3rd. Plug at 950' w/100 sxs.
4th. Plug at 290' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

RECEIVED
MAR 16 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

Form CP-2/3

MAR 09 2011