

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01766-00-00
Spot: NESENE SW Sec/Twnshp/Rge: 32-11S-15W
1733 feet from S Section Line, 2908 feet from E Section Line
Lease Name: BOOTH Well #: 8
County: RUSSELL Total Vertical Depth: 3206 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2995		
SURF		0		
PROD	5.5	3199	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2011 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: PETROLEUM PROPERTY SERVICE Phone: (316) 265-3351

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 600# hulls.
Shoot perfs at 1550' - 900' - 425'.
CIBP at 2995'.
Squeeze well at 1261' to 1330' with 450 sxs cement.
Well is now bridged off at 1500'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2011 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1500' - pumped 220 sxs cement - hole on strong vacuum - ran out of cement, went to town for more cement.
Pulled tubing to 900' - pumped 100 sxs cement with 300# hulls.
Pulled tubing out - tied onto casing and pumped 25 sxs cement.
Full - shut in with 200# P.S.I.

Perfs:


Top	Bot	Thru	Comments
3199	3202		REAGAN SAND
3190	3195		BSL PENN

Remarks: ALLIED CEMENTING COMPANY-TICKET #34119.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

RECEIVED *cm*

MAR 03 2011 CP-2/3

KCC WICHITA *3/18*

MAR 02 2011