

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21362-00-00  
Spot: SWNWSESW Sec/Twnshp/Rge: 32-11S-15W  
940 feet from S Section Line, 3680 feet from E Section Line  
Lease Name: BOOTH Well #: 9  
County: RUSSELL Total Vertical Depth: 1768 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	809	0	w/400 sxs cmt
PROD		0		

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2011 8:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1559

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel - 1100# hulls - 28 sxs gel.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2011 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 1768' - pumped 28 sxs gel - followed with 80 sxs cement with a total of 400# hulls. WOC.  
Pulled tubing to 1297' - pumped 100 sxs cement with 450# hulls. WOC.  
Pulled tubing to 1060' - pumped 300 sxs cement with 250# hulls - cement circulated to surface. POOH. Topped off with 30 sxs cement.  
Checked on 03/02/2011 - cement down one foot.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #38713.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

MAR 08 2011

Form CP-2/3

3/18

MAR 03 2011

KCC WICHITA