

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24773-00-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 25-19S-24W  
285 feet from S Section Line, 4841 feet from E Section Line  
Lease Name: LAAS 'KT' Well #: 1-25  
County: NESS Total Vertical Depth: 4448 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		WITH 170 SX CMT
PC		1621		CMT CIRCULATED
PROD	4.5	4445	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2011 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BILLY DAUGHERTY Company: PINTAIL PETROLEUM Phone: (785) 798-3641

Proposed  
Plugging  
Method:

PLUG AT 4400' WITH 50 SX CMT. PLUG AT 1650' CIRCULATE CMT TO SURFACE. CHECK ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2011 12:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4200' & PUMPED 100# HULLS & 50 SX CMT. PULLED TBG TO 1650' & CIRCULATED CMT TO SURFACE WITH 150 SX CMT. PULLED TBG & TOPPED OFF WITH 30 SX CMT. TIED ONTO 8 5/8" X 4 1/2" ANNULUS & PUMPED 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4408	4410		MISSISSIPPI
4400	4402		MISSISSIPPI
4284	4288		CHEROKEE SAND
4276	4281		CHEROKEE SAND

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
MAR - 1 2011  
KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
MAR 10 2011  
KCC WICHITA

Form Cr 2/3

3/18