

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20445-00-00  
Spot: NESENE Sec/Twnshp/Rge: 10-25S-21W  
3662 feet from S Section Line, 324 feet from E Section Line  
Lease Name: LANCASTER A Well #: 1  
County: FORD Total Vertical Depth: 4734 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 686        |             | WITH 300 SX CMT |
| PROD   | 5.5   | 4733       | 1978        | WITH 200 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2011 10:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: INNES PHILLIPS Company: PINTAIL PETROLEUM Phone: (316) 263-2243

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT 4600' & @ 4100'. PLUG AT 1430' WITH 15 SX GEL & 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2011 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 25 SX CMT WITH 2% CC AT 4600' & AGAIN AT 4100'. 1ST PLUG AT 1430' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH 20 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4667 | 4681 |      | CHEROKEE |
| 4143 | 4146 |      | LANSING  |

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
MAR - 8 2011  
KCC DODGE CITY

RECEIVED  
MAR 09 2011  
KCC WICHITA

Form 2-23

3/18