

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-181-20508-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 10-8S-37W
2781 feet from S Section Line, 2860 feet from W Section Line
Lease Name: QUENZER Well #: 1-GW
County: SHERMAN Total Vertical Depth: 875 feet

Operator License No.: 33766
Op Name: QUENZER, ALLEN
Address: 3440 RD 66
BREWSTER, KS 67732

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	297	0	125 SX CMT
PROD	4.5	723	0	75 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2011 1:15 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ALLEN QUENZER Company: QUENZER, ALLEN Phone: (785) 694-2497

Proposed Plugging Method: Ordered 100 sxs cement and 50# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2011 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

7" surface casing set at 297' w/125 sxs cement.
4 1/2" production casing set at 723' w/75 sxs cement.
TD 875'. Production casing set to top of Niobrara. Drilled through Niobrara to 875'.
Well reported to be non-commercial.
Ran tubing to 740' - pumped 55 sxs cement mixed with 50# hulls - cement to surface.
Pulled tubing to surface. Connected to 4 1/2" casing - pumped 15 sxs cement.
7" surface casing was observed to be full of cement.

Remarks: ALLIED CEMENTING COMPANY-TICKET #41005.

Plugged through: TBG

RECEIVED
MAR 01 2011
KCC WICHITA

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

Form CP-2/3

✓ 3/16

FEB 24 2011