

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20368-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 36-17S-13W
990 feet from N Section Line, 2970 feet from W Section Line
Lease Name: LAWRENCE Well #: 3-D
County: BARTON Total Vertical Depth: 3364 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250	0	175 sxs
PROD	5.5	3363	0	75 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2011 10:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls - 12 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1500' - 750' - 245'.
Ran tubing to 3350' - tied to tubing - pumped 12 sxs gel - followed with 50 sxs cement with 200# hulls.
Pulled tubing to 1500' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 725' - circulated cement to surface on casing and surface pipe with 150 sxs cement with 200# hulls.
Pulled tubing and topped off with 5 sxs cement.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN) RECEIVED *CR*

MAR 03 2011 Form CP-2/3

KCC WICHITA *3/1/11*

FEB 23 2011