

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21546-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 31-21S-15W  
2998 feet from S Section Line, 1673 feet from E Section Line  
Lease Name: MULL Well #: 1  
County: PAWNEE Total Vertical Depth: 3906 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3850		WITH 2 SX CMT
SURF	8.625	974		WITH 450 SX CMT
PROD	5.5	3900	2132	WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/18/2011 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2540

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2011 9:20 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3850' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1000' WITH 100# HULLS, 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3900	3906	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
MAR 10 2011  
KCC WICHITA

RECEIVED  
MAR - 1 2011  
KCC DODGE CITY

Form CPS 2/3  
3/18