

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23,802 ⁻⁰⁰⁻⁰⁰
SW $\frac{1}{4}$, Sec. 5, T 13 S, R 18 W/R
330 feet from N/S section line
300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7064
Operator: Cattlemans Oil Operations
Name & Box 39
Address Hays, Ks. 67601

Lease Name Staab Well # 1
County Ellis
Well Total Depth 3810 feet 123.82
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 $\frac{5}{8}$ feet 208

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number _____

Address Box 1389, 1105 Walnut, Great Bend, Ks. 67530

Company to plug at: Hour: 1:00 AM Day: 23rd Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Allan Carris

(company name) Allen Drilling (phone) (316) 793-5681

were: 8 $\frac{5}{8}$ " - 208' S.P. CUC w/150 sks common- 2% gel - 3% cal. cl. (by Allied Cmt)
order 185 sks 50/50 pozmix 4% gel 3% cal. cl. 1 sk cello-flake and 8 $\frac{5}{8}$ " plug spot
with drill stem. Turn hole over-heavy mud between all plugs no show or blow- no
circulation problems, Elev. 2174' Anhy. 1460' did not find ar buckle

Signed *Marcus Schmidt*
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00 AM Day: 23 Month: February Year: 19 84

ACTUAL PLUGGING REPORT Ordered 185 sks 50/50 pozmix 4% gel 3% cal. cl. - 1 sk cello-
flake and 8 $\frac{5}{8}$ " plug. Spotted with drill stem - turned hole over - heavy mud
between all plugs.

1st plug @ 1470' w/25 sks

2nd plug @ 780' w/100 sks w/1 sk cello-flake

3rd plug @ 240' w/40 sks

4th plug solid bridge -hulls - plug @ 40' w/10 sks cmt. 10 sks in Rat Hole (Circulate)
Remarks: _____

Cemented by Allied Cementing Company)

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1984
2-27-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed *Marcus Schmidt*
(TECHNICIAN) DOIC

3-2-84
0495
2-23