

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21991-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 11-18S-8W  
4218 feet from S Section Line, 2439 feet from E Section Line  
Lease Name: ROSS B TWIN Well #: 1  
County: RICE Total Vertical Depth: 3250 feet

Operator License No.: 6988  
Op Name: SMITH, RICHARD E. DBA SMITH OIL O  
Address: 327 W 4TH PO BOX 550  
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	219		130 sxs
PROD 7		3247	1080	100 sxs

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2011 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/03/2011 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3200' AND CAP WITH 7 SX'S CEMENT. CUT CASING AT 1080' AND PULL TO 1025' AND PUMP 50 SX'S CEMENT WITH 100 #'S COTTON HULLS, PULL CASING TO 775' AND PUMP 50 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 270' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3247	3250	CSG	CASING

Remarks: 60-40 POZ, 4% GEL. COPELAND CEMENT TICKET #C-37546.

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

RECEIVED

MAR 14 2011

KCC WICHITA

Form CP-2/3

3/18

124