

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23719-00-00
Spot: SESESE Sec/Twnshp/Rge: 29-9S-21W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: HILL Well #: 1
County: GRAHAM Total Vertical Depth: 3983 feet

Operator License No.: 34392
Op Name: TEXKAN EXPLORATION LLC
Address: PO BOX 191643
DALLAS, TX 75219

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/26/2011 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK Company: TEXKAN EXPLORATION LLC Phone: (785) 216-0064

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 02/26/2011 4:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 3900' w/25 sxs.
2nd. Plug at 1830' w/25 sxs.
3rd. Plug at 1050' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Case Morris
(TECHNICIAN)

FEB 28 2011

RECEIVED Form CP-2/3
MAR 03 2011 ✓ 3/18
KCC WICHITA