

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20402-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 24-14S-11W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: STOPPEL Well #: 4  
County: RUSSELL Total Vertical Depth: 2920 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	277	0	w/165 sxs cmt
PROD	4.5	2917	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2011 9:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perf: 250' - 600' - 1400'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/28/2011 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2700' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1200' - pumped 80 sxs cement with 100# hulls - cement circulated.  
POOH. Hooked up to casing and pumped 25 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Hooked up to casing and pumped 15 sxs cement.  
Max. P.S.I. 350#. Ring blew off - topped off with cement.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4763.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN) RECEIVED

CM

MAR 03 2011 Form CP-2/3

KCC WICHITA

3/1/11

MAR 01 2011