

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23542-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 19-30S-15W
870 feet from N Section Line, 1090 feet from E Section Line
Lease Name: GIBSON UNIT Well #: 1-19
County: BARBER Total Vertical Depth: 4730 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4540		WITH 2 SX CMT
SURF	8.625	212		WITH 190 SX CMT
COND	13.63	102		WITH 110 SX CMT
PROD	5.5	4703	3905	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2011 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: DUSTIN WYER Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 02/25/2011 1:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4540' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4610	4632		
4592	4604		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

RECEIVED

MAR 10 2011

KCC WICHITA

District: 01

RECEIVED

FEB 28 2011

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

Form CP-23

3/18