

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23634-00-00

Spot: S2SWNWNE

Sec/Twnshp/Rge: 34-34S-11W

1120 feet from N Section Line, 2310 feet from E Section Line

Lease Name: KERSTEN

Well #: 1-34

County: BARBER

Total Vertical Depth: 5065 feet

Operator License No.: 5822

Op Name: VAL ENERGY, INC.

Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4650		WITH 2 SX CMT
SURF	8.625	209		WITH 190 SX CMT
PROD	5.5	4799	3098	WITH 125 SX CMT

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/16/2011 8:30 AM

Plug Co. License No.: 34082

Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: DUSTIN WYER

Company: VAL ENERGY

Phone: (316) 263-6688

Proposed
Plugging
Method:

SET CIBP @ 4650' & PUT 2 SX CMT ON TOP OF CIBP. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: NONE

Date/Time Plugging Completed: 02/16/2011 9:20 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4650' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4732	4742		MISS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG


RECEIVED

MAR 01 2011

KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

FEB 17 2011

KCC DODGE CITY

Form CP-2/3

3/18